BANGALORE CITY MUNICIPALITY.

Notice dated 2nd July 1895.

Sealed tenders are invited for the collection and consolidation of materials for the following roads within the City Municipal limits and will be received up to the 15th instant.

				Rs.
Recoating	4	furlongs of the	Cunningham road (Lateriting)	.. 1,260
Do	4	do	Albert Victor road (Lateriting)	. 1,260
Do	2½	do	Miller's road (Lateriting)	.. 650
Do	3	do	Srinivasacharlu's road (Jungle metal)	.. 690
Do	9	do	Subedar Chattram road (Jungle metal)	.. 2,070
Do	3	do	Balepete road (Jungle metal)	.. 690
Do	3	do	Agrahar tank bund road (Jungle metal)	.. 690
Do	11	do	Avenue Cathcart road (Lateriting)	.. 3,967
Do	5½	do	Fort Gate Hosur road (Jungle metal)	.. 1,357
Do	5½	do	Post Office road (Jungle metal)	.. 1,703

2. Further particulars can be obtained from the Municipal Office during office hours on all days except holidays.

K. SRINIVASA ROW, *Vice-President.*

MYSORE CITY MUNICIPALITY.

Proceedings of the adjourned Special Meeting of the Municipal Commissioners held at the Town Hall on Saturday the 8th June 1895 at 7 A. M.

Present.	*Absent.*
H. Nanjundaraj Aras Esq., Vice-President.	B. K. Venkatavaradaiengar Esq., President.
The Principal of the Maharaja's College, Mysore.	The Civil Surgeon, Mysore.
The Amildar of Mysore.	The Executive Engineer, Mysore.

Commissioners.

M. Venkatakrishnaiya Esq.	Fathekhan Esq.
M. L. Narasimhaiengar Esq.	Standish Lee Esq.
W. P. Narainsami Mudaliar Esq.	A. Annaiya Pandit Esq.
A. Ramanna Esq.	H. Lingaraj Aras Esq.
H. Krishna Rao Esq.	B. Linganna Esq.
Syed Gulam Dastagiri Saib Esq.	H. Ranganna Esq.
Rahamatula Sait Esq.	J. Timmegauda Esq.

Subjects.

I. Government Proceedings No. 21089-90—L. F. 40-92, dated 21st May 1895 (1) ordering that the Board may recommend to the Government the appointment of two additional members, one for each of the Devaraj and Fort Mohallas, as it would entail further delay if a fresh election is to be held; and (2) inviting the opinion of the Board on the amendment of Sections 3 and 5 of the Municipal Regulation to make clear their meaning.

Before commencing the Proceedings of the meeting Mr. M. L. Narasimhaiengar made the following proposal, being seconded by Mr. Venkatakrishnaiya:—

That subject No. 5 be taken first and discussed before the 1st subject is taken, as that has some reference to the recommendation to be made for the Municipal Commissionership of the Fort Mohalla, involved in proposition No. I.

Mr. J. Weir proposed an amendment, being seconded by Mr. A. Ramanna, that the first question should be discussed first, as the matter is urgent.

The amendment was carried by a majority.

Mr. M. L. Narasimhaiengar proposed that the first proposition may be adjourned and a recommendation be submitted to Government for a fresh election, as that would be more satisfactory.

Mr. Venkatakrishnaiya, seconded the above proposition.

Amendment proposed by Mr. A. Ramanna is that as the Government has finally settled that there need not be any election but that the member should be recommended by the Board, no adjournment is necessary.

Messrs. Raju Mudaliar, the Amildar of Mysore Taluk, and J. Weir seconded the above proposal.

Amendment was carried by a majority.

Mr. A. Ramanna proposed that Mr. Nail Narain Rao be recommended to Government for the vacant Municipal Commissionership of the Fort Mohalla.

As none seconded the proposal it was thrown out.

Proposed by Mr. Raju Mudaliar and seconded by Mr. Narainsami Mudaliar that Mr. Mallikarjunaiya, be recommended to be appointed as Municipal Commissioner for Fort.

It was not carried, as only three voted in favor of the proposition against five.

Mr. M. L. Narasimhaiengar, being seconded by Mr. Venkatakrishnaiya, proposed that Mr. C. Krishnaiengar be recommended as Municipal Commissioner for Fort.

Four voted for the proposition and the other four voted against it. The casting vote was given against the proposition.

Mr. J. Weir did not give his vote on either side, on the ground that Mr. C Krishnaiengar is not fully qualified to become a Municipal Commissioner as per election rules.

Proposed by Mr. A. Ramanna and seconded by Messrs. Dastagiri Saib and Raju Mudaliar that Mr. K. Mailar Rao B.A., and B.L., be recommended to Government as Municipal Commissioner for Fort.

Resolved that Mr. Mailar Rao be recommended for the vacant Municipal Commissionership of Fort by a majority, Mr. J. Weir being neutral on the ground already given above.

Proposed by Mr. Venkatakrishnaiya and seconded by Mr. M. L. Narasimhaiengar that Mr. H. Krishna Rao, be recommended to Government for Devaraj Mohalla.

Carried nem-con.

(2) Proposed by Mr. J. Weir seconded by Mr. Venkatakrishnaiya and that a Sub-Committee may be appointed to call for the records and submit a report to be placed before the next meeting regarding the 2nd para of the Government Proceedings No. 21089-90—L. F. 40-92, dated 21st May 1895.

Resolved that a Sub-Committee composed of Messrs. Ramanna, Venkatakrishnaiya, M. L. Narasimhaiengar, H. Krishna Rao, and the Vice-President be formed to submit a report.

II. Proposal by Dr. Benson "that the town of Mysore is in urgent need of a poor-house and ward for incurables, as at present the Civil Hospital wards are more or less filled up with people who are destitute and who require food rather than medical attendance."

Resolved that as the proposer is absent this be deferred to the next meeting.

III. The application from Applachar, Municipal Public Works Overseer, stating that as he was promised an annual increment of Rs. 10 up to 70, with horse allowance of Rs. 15, he accepted the post in October 1892 on Rs. 50 plus 10 horse allowance, but nothing was done though two years had passed away, and praying that his pay may be raised to Rs. 70 plus 15 horse allowance. Adjourned to next meeting.

IV. Proposal by Messrs. M. L. Narasimhaiengar and M. Venkatakrishnaiya "that although the personal merits of Mr. Sundram Iyer, Municipal Engineer, are unquestionable, having regard to the pressure on Municipal revenue and the nature and extent of our Public Works, it is proper to recommend to Government to abolish the Engineer's appointment for the Mysore Municipality."

Adjourned.

V. Government Proceedings No. 14885—L. F. 40-92, dated 16th March 1895, calling for report on the petition of Mr. C. Krishnaiengar, as to whether any modification of the Election Rule 5 (clause E) so as to declare persons paying a shop rent of Rs. 100 eligible for Municipal Commissionership is necessary.

Resolved that the proposition be referred to the above named Sub-Committee for report.

ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received at the Municipal Office, Mysore, up to the 30th July 1895, for the supply of materials for road repairs and stone drains, to be done in the Town, (within Municipal limits) during the official year 1895-96.

2. The details of materials required and the approximate quantities required of each are shown in the annexed statement, which quantities however are not guaranteed. The materials should be exactly as described in the specifications in the Municipal Engineer's office, and similar or superior to the samples which are kept in his office.

3. Tenders should be submitted in the form which will be shown in the Municipal Office, accompanied by a schedule showing the rates at which the different kinds of materials will be supplied. They may be submitted for all or any of the materials mentioned below.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for the collection of materials for road repairs and drains during 1895-96," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the President of the Municipality, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender, or to accept in any tender the tender for all the materials together or none which one has tendered for.

6. Within eight days of the acceptance of any tenders the successful competitor or competitors will be required to execute a contract bond (in the form which may be seen in the office) and to deposit the sum of Rs. 200 with the Municipality as a security for the due performance of the contract.

7. The names of the successful competitors whose tenders have been accepted will be posted on the notice Board in the Municipal Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On the acceptance of any of the tenders the earnest money on rejected tenders will be returned.

Statement of materials required.

Items.	Approximate quantity required.	Remarks.
Collecting and stacking quartz metal broken to size as per specification. C. Yds.	4,000	The rates to include cost of carting to the road side anywhere within Municipal limits and stacking in heaps of dimensions as per specifications not less than $\frac{1}{6}$th of the schedule quantities will be required to be collected in each month.
Ditto do black granite of Purnaiya's Nala excavations .. C. Yds.	3,000	
Ditto do gravel .. ditto	7,000	
Burnt slab stones 3″ thick including filling as in drains, &c. .. S. Ft.	10,000	The rates to include dressing and fixing at the places ordered.
Ditto do 6″ thick for covering over drains and tunnels . S. Ft.	2,000	
New rough stone work .. C. Yds.	300	The rate to include construction wherever ordered.

H. NANJUNDARAJ URS, *Vice-President.*

ALALKATTE CHANNEL DIVISION.

Notice dated the 27th June 1895.

Notice is hereby given that sealed tender will be received at the office of the Executive Engineer, Alalkatte Channel Division, Saligram, up to Saturday the 20th July 1895, for extending the Saligram Rai Channel in the Yedatore Taluk, Mysore District.

2. The proposed extension is about 12 miles long besides 12 miles of branch Channels. It must be completed in all respects including branch channels, before the close of May 1897.

3. The work will be divided into six sections and intending contractors may tender for one or more sections. An approximate estimate of the quantities of different kinds of work in each section is given below.

4. The specification of work and conditions of contract may be seen in the office of the Chief Engineer at Bangalore or of the Executive Engineer at Saligram. The sections of the channel and designs for masonry works may be seen at the Executive Engineer's office at Saligram, between the hours of 12 noon and 5 P.M., every day.

5. Tenders should be accompanied by a schedule of rates for the different classes of works, and must be superscribed "Tenders for extending Saligram Rai Channel."

6. Each tender should be accompanied by a deposit of Rs. 1,000 in cash or Government Currency Notes, in default of which such tender will be rejected.

7. The final acceptance of any tender will rest absolutely with the Chief Engineer, and no enquiries regarding the rejection of any tender will be answered.

8. The names of successful tenderers will be posted on the notice board in the Executive Engineer's Office, and intimation will be given to them. Their postal address should be enclosed with their tenders.

9. Within ten days of the acceptance of any tender, the tenderer should execute the usual contract bond and hand it over to the Executive Engineer, in defaullt of which his tender is liable to be cancelled and his deposit money forfeited to Government.

10. The deposit money of unsuccessful tenderers will be returned to them on application after the 5th of August 1895.

Items of work.	Per.	Main Channel.			Branch Channel.		
		No. 1 Section 0 to 3 M. 47·74 chs.	No. 2 Section 3 M. 47·74 to 6 M. 50·88 chs.	No. 3 Section 6. M. 50·88 to 12 M. 9·40 chs.	No. 4 Section Bichanhalli 0 to 4 miles.	No. 5 Section Gundanhalli (South) 0 to 3 M. 182·00 chs.	No. 6 Section Gundanhalli (North) 0 to 3¾ miles.
Cutting Channel—							
Earth	C. Yds.	31,489	13,317	19,836	5,361	9,603	10,489
Gravel	,,	18,895	13,185	31,351	7,575	13,569	14,817
Soft rock	,,	50,847	32,231	12,939	1,166	2,089	2,664
Hard rock	,,	7,394	17,683	3,545	458	764	1,090
Channel Stones—							
Mile stones	Each.	3	3	5	4	3	3
Grade stones	,,	186	144	98	64	56	60
Index stones	,,	184	140	95	60	53	57
Bank stones	,,	..	..	48	..	..	..
Bed stones	,,	..	..	50	..	..	..
Road bridges & cart panaboos—							
Excavation	C. Yds.	488	164	200	..	73	172
Concrete	C. Ft.	3,541	1,229	1,150	..	362	916
Slabs	,,	..	..	..	..	367	930
Raw and burnt stone slabs for pillers, &c.	,,	3,587	1,245	1,152	..	..	..
Gravelling for road way	,,	1,126	390	334	..	107	306
Plastering	Sq.	27·28	9·47	11·31	..	3·67	7·34
Burnt stone in surki mortar ..	C. Ft.	15,158	5,623	7,932	..	3,422	7,824
Burnt brick in surki morter	,,	1,568	553	665	..	217	434
Waste weirs and silt dams—							
Excavation	C. Yds.	1,025	526	967	..	135	270
Brick in surki mortar	C. Ft.	6,316	3,306	6,264	..	917	1,834
Rough stone pitching dry	C. Yds.	803	463	910	..	130	260
Slab stone 6″ thick	C. Ft.	345	171	298	..	38	76
Concrete	..	345	171	298	..	38	76
Irrigation sluices—							
(As per standard design)	No.	15	12	22	16	..	..
Channel embankment—							
Wherever required ..	C. Yds.	..	..	..	18,014	4,213	36,118
Head sluice vent (3×4½)—							
Clearing site	L. S.	..	..	..	..	Rs.	Rs.
Excavation	C. Yds.	..	..	..	..	58	87
Burnt stone in surki mortar	C. Ft.	..	..	..	..	1,712	2,568
Burnt brick do	,,	..	..	..	..	2,624	3,936
Archwork	,,	..	..	..	..	104	156
Cornice	R. Ft.	..	..	..	..	126	189
Concrete	C. Ft.	..	..	..	..	6	9
Plastering	Sq.	..	..	..	..	13·92	20·88
Teak wood work	C. Ft.	..	..	..	..	22	33
Gear rod, &c.	L. S.	..	..	..	..	Rs.	Rs.
Slab 3″ thick	C. Ft.	..	..	..	..	164	246
Do 6″ do	,,	..	..	..	..	72	108
Do 12″ do	,,	..	..	..	..	74	111
Cut stone in surki mortar	,,	..	..	..	..	122	183
Pointing	Sq.	..	..	..	..	2·36	3·54

C. A. MAHADEVA SASTRI,
Executive Engineer.